



PLAN NOTES

- 1 EXISTING CMU WALL, TYPICAL.
- 2 EXISTING METAL DOOR & FRAME, TYPICAL.
- 3 EXISTING TOILET, TYPICAL.
- 4 EXISTING SINK, TYPICAL.
- 5 PROVIDE NEW TOILET PARTITIONS, TYPICAL. REMOVE EXISTING PARTITIONS. NOTE DOOR SIZES SHOWN ON PLAN.
- 6 EXISTING TROUGH URINAL.
- 7 EXISTING DRINKING FOUNTAIN.
- 8 EXISTING ROLL-UP COUNTER DOOR.
- 9 CONTROL JOINT, TYPICAL. SLOPE CONCRETE 1/4" PER FOOT MINIMUM.
- 10 NEW CHAIN LINK FENCE - MATCH EXISTING. SEE SHEET A100 FOR CONTINUATION.
- 11 NEW 4'-0", SWING CHAIN LINK FENCE GATE.
- 12 REMOVE EXISTING 6'-0" SWINGING CHAIN LINK FENCE GATE. INFILL OPENING W/ CHAIN LINK FENCING TO MATCH EXISTING. THIS WORK IS INCLUDED IN BID 2 ITEMS.
- 13 SURFACE LIGHTING FIXTURE SD-1, TYPICAL. EXTEND POWER FROM NEAREST LOCATION (FIELD VERIFY).
- 14 PHOTOCELL CONTROL W/ SWITCH OVERRIDE IN JANITOR ROOM.
- 15 PROVIDE LOUVER W/ INSECT SCREEN IN SOFFIT. SIZE SO THAT FREE AIR AREA EQUALS EXISTING WALL MOUNTED LOUVER - FIELD VERIFY.
- 16 EXISTING BUILDING ROOF TRUSSES, TYPICAL.
- 17 NEW ROOF TRUSSES @ 24" ON CENTER, TYPICAL.
- 18 NEW 2 x OUTRIGGERS @ 24" ON CENTER, TYPICAL.
- 19 NEW GABLE TRUSS.
- 20 REMOVE EXISTING PLYWOOD SHEATHING & REPLACE W/ NEW 5/8" CDX SHEATHING W/ SHTG CLIPS @ MID-SPAN. PROVIDE 8d @ 6" O.C. AT PANEL EDGES & 8d @ 12" O.C. AT INTERMEDIATE FRAMING. PROVIDE BLKG AT ALL PANEL EDGES. TYPICAL BOTH A & B BUILDINGS.
- 21 REMOVE EXISTING METAL ROOFING & DISPOSE ALL DEBRIS OFF SITE & REPLACE W/ NEW ASPHALT SHINGLES & ICE/WATER UNDERLAYMENT, TYPICAL BOTH A & B BUILDINGS.
- 22 REMOVE EXISTING GUTTERS & REPLACE W/ NEW TO MATCH EXISTING, TYPICAL BOTH A & B BUILDINGS.
- 23 REMOVE EXISTING EAVE BOARDS & REPLACE W/ NEW TO MATCH EXISTING, TYPICAL BOTH A & B BUILDINGS.
- 24 REMOVE EXISTING RAKE BOARDS & REPLACE W/ NEW TO MATCH EXISTING, TYPICAL BOTH A & B BUILDINGS.
- 25 REMOVE EXISTING DOWNSPOUT. PROVIDE NEW 3" DIA. PVC DOWNSPOUT, TYPICAL BOTH A & B BUILDINGS. CONNECT DOWNSPOUTS TO EXISTING DRAINAGE SYSTEM, TYPICAL.
- 26 PROVIDE 4-PLY GFCI RECEPTACLE W/ WEATHERPROOF COVER & CONDUIT. SURFACE MOUNTED 18" ABOVE CONCRETE SLAB.
- 27 REPLACE EXISTING METAL FLASHINGS AT ROOF PENETRATIONS W/ NEW GALVANIZED FLASHINGS AS REQ'D. TYPICAL BOTH A & B BUILDINGS.

PLAN NOTES

- 1 REMOVE & DISPOSE OF ALL DEBRIS OFFSITE, TYPICAL.
- 2 SEE PAINT SCHEDULE IN SPECIFICATIONS.

ELEVATION NOTES

- 1 EXISTING CMU. PAINT AS SPECIFIED.
- 2 EXISTING METAL ROOF STRUCTURE, TYPICAL.
- 3 NEW ASPHALT SHINGLE ROOF ASSEMBLY W/ RIDGE VENT, TYPICAL.
- 4 NEW GUTTER & EAVE BOARD, TYPICAL. MATCH EXISTING. PAINT AS SPECIFIED.
- 5 NEW RAKE BOARD, TYPICAL. MATCH EXISTING. PAINT AS SPECIFIED.
- 6 NEW PVC DOWNSPOUT, TYPICAL. PAINT AS SPECIFIED.
- 7 EXISTING METAL DOOR & FRAME, TYPICAL. PAINT AS SPECIFIED.
- 8 EXISTING ROLLING COUNTER DOOR.
- 9 EXISTING METAL SIDING, TYPICAL. PAINT AS SPECIFIED.
- 10 NEW METAL SIDING TO MATCH EXISTING. PAINT AS SPECIFIED.
- 11 EXISTING FOOTBALL SCOREBOARD. REMOVE TO ALLOW NEW ROOF WORK. AFTER ROOF WORK IS COMPLETE, REINSTALL IN SAME LOCATION USING SAME METAL ANGEL FRAMING, ETC. PREP & PAINT SUPPORT FRAMING AS SPECIFIED. BED SUPPORT ANGLES IN SEALANT WHERE BEARING ON NEW ROOF. PROVIDE NEW HDG FASTENERS TO MATCH EXISTING. PLACE SUPPORT ANGLES ON ROOF OVER EXIST-TRUSSES, TYPICAL. FIELD VERIFY ALL EXISTING CONDITIONS.

PERMIT SET

REVISIONS		
no	date	by
-	-	-

3399 REGISTERED ARCHITECT
Alan E. Gozart
ALAN E. GOZART
STATE OF WASHINGTON

project number 22-06
date 3.30.2023
file name 2206PSE
drawn by ACG
checked by AEG
title

Floor & Roof Plans, Bldg Section, Ext. Elevations, Details & Notes

A210